



Case Study

Land Remediation

Project Name: Mayfair Mews, Little Venice, Mayfair, London.

Project Value: £380,000.00

Project Brief

To excavate and dispose of asbestos contaminated soils circa 20,250 m³

The project involved installing a piling system 14 metres below ground level, then systematically installing C24 structural timber shoring as the excavation proceeded, due to the close proximity of housing this was carried out in a methodical method ensuring all aspects of Health and Safety were met at all times throughout this project.

Furthermore we had to devise a system to get the contaminated soils out of the vicinity of the site due to the narrow entrance/exit which we utilised a conveyor belt system to our waiting tippers situated on the main road to the site to ensure this project could be completed within the timescales that our client requested.

Due to the meant the excavators had to be dismantled and transported through the entrance and then reassembled within the confines of the site, this project was completed within the timescale and budget to our clients satisfaction.



